

The Stellar Populations of Low-redshift Clusters

Craig Harrison¹, Matthew Colless², Warrick J. Couch³
 and B. A. Peterson¹

¹Mount Stromlo Observatory, The Australian National University, Cotter Road, Weston, ACT 2611, Australia email: harrison@mso.anu.edu.au, peterson@mso.anu.edu.au

²Anglo-Australian Observatory, PO Box 296, Epping, NSW 1710, Australia
 email: colless@aao.gov.au

³School of Physics, University of New South Wales, Sydney NSW 2052, Australia
 email: wjc@phys.unsw.edu.au

Abstract. We present some preliminary results from an on-going study of the evolution of stellar populations in rich clusters of galaxies. Our baseline sample contains core line-strength measurements from 183 galaxies with $b_J \leq 19.5$ from four clusters with $\bar{z} \sim 0.04$, against which observations of higher-redshift clusters can be compared. Using predictions from stellar population models to compare with our measured line strengths we can derive *relative* luminosity-weighted mean ages and metallicities for the stellar populations in each of our clusters. It must be stressed that these ages and metallicities are only accurate when used in an relative sense as the stellar population models, due to differing abundance ratios used in the models compared to those observed in elliptical galaxies, provide inaccurate absolute ages and metallicities. We also investigate the $Mgb'-\sigma_0$ and $H\beta'_G-\sigma_0$ scaling relations. We find that Mgb' is correlated with σ_0 , the likely explanation being that larger galaxies are better at retaining their heavier elements due to their larger potentials. $H\beta'_G$, on the other hand, we find to be anti-correlated with σ_0 . This result implies that the stellar populations in larger galaxies are older than in smaller galaxies.

1. Introduction and Observations

The formation and evolution of clusters of galaxies and of their early-type galaxy population is a topic of active debate. Studying the integrated light from stellar populations can help to discriminate between models of giant elliptical galaxy formation: the monolithic collapse model (Eggen et al., 1962) in which giant elliptical galaxies form rapidly in a process that can essentially be considered a single collapse and the hierarchical merging model (Searle & Zinn, 1978) in which giant elliptical galaxies are built up over a long timescale by distinct merger events. If it was found that early-types were largely coeval in clusters then this would favour the monolithic collapse model, whereas a large spread in ages would favour hierarchical merging.

Increasing a galaxy's age by a factor of two while decreasing its metallicity by a factor of three results in a spectrum almost indistinguishable from the original (Worthey, 1994). This age/metallicity degeneracy can be partially broken by comparing age-sensitive spectroscopic indices with metallicity-sensitive spectroscopic indices. By plotting two such indices against each other and comparing the results to stellar population models (e.g. Worthey, 1994; Thomas et al., 2003) we can determine the mean relative luminosity-weighted age and metallicity of a given stellar population.

Previous work in this area has concentrated on individual clusters such as Coma (Jørgensen, 1999; Moore et al., 2002) and Fornax (Kuntschner, 2000) with sometimes




Figure 1. $H\beta_G$ equivalent width versus $[MgFe]$ equivalent width. Thomas et al. (2003) stellar population model grids have been overlaid on data from the Coma cluster (*left*) and Abell 1139 (*right*).

conflicting results coming from the same cluster, e.g. Gonzalez et al. (1993) and Moore et al. (2002). Coma and Fornax represent the extremes of the cluster richness scale and this project will study clusters that fill in this range. We will study, in detail, the stellar populations in several low-redshift ($z \sim 0.04$) clusters from the core out into the surrounding structures. These results will then be used as a comparison for observations of a range of higher-redshift clusters ($0.3 \leq z \leq 0.55$), allowing us to draw conclusions about the formation and evolution of the stellar populations in rich clusters.

Line-strength measurements, redshifts and velocity dispersions were obtained for 183 galaxies from four clusters over three nights in April 2002 with the 2dF system on the 3.9m AAT. The sample was selected from galaxies with $b_J \leq 19.5$, within a 2° diameter FOV centred on each of the clusters and within a 3σ redshift range centred on the cluster redshift. The 300B grating ($\sim 9\text{\AA}$ FWHM) was used to obtain a wide spectral range covering as many indices as possible, while the 1200V grating ($\sim 2\text{\AA}$ FWHM) was used to obtain higher resolution spectra yielding precise velocity dispersions.

2. Ages and Metallicities

Comparison of the measured equivalent widths of $H\beta_G$ and $[MgFe]$ for two of our clusters, Coma and A1139, and predictions from the Thomas et al. (2003) stellar population models is shown in Fig. 1. Using these models we obtain relative ages and metallicities for our stellar populations. We find that Coma cluster galaxies have a mean age of 9.3 ± 3.8 Gyr with a mean metallicity of 0.15 ± 0.23 dex relative to solar. A1139, we find, has a mean age of 10.3 ± 3.4 Gyr with a mean metallicity of 0.12 ± 0.41 dex relative to solar. Refinements still need to be made to the data set and the other clusters need to be analysed before any conclusions can be drawn. The age/metallicity degeneracy is quite evident from these plots. Also, there seems to be some disagreement between our observations and the models. The data points with low $H\beta_G$ equivalent widths could be star-forming galaxies, which we wish to exclude from this part of the analysis. By examining each galaxy's spectra for emission lines indicative of a star-forming galaxy and by measuring $H\alpha$ equivalent widths we can eliminate these galaxies from our sample.




Figure 2. Scaling relations in low-redshift clusters. (*left*) The Mgb' versus σ_0 relation; the solid line is our fit to the data and the dashed line is that from Colless et al. (1999). (*right*) The $H\beta'_G$ versus σ_0 relation; the solid line is our fit to the data and the dashed line is that from Kunstchner (2000). The symbols are the same for both figures: circles represent galaxies from Coma, squares from A1139, triangles from A3558 and crosses from A0930.

3. Scaling Relations

In Fig. 2 we show the Mgb' (the dash denoting that the index value has been converted from Angstroms to magnitudes) and $H\beta'_G$ versus central velocity dispersion (σ_0) scaling relations for all four of our clusters. The solid line in both plots are our robust fit to the data from all four clusters while the dotted lines are fits taken from the literature.

We find that $H\beta'_G$ is anti-correlated with σ_0 and find good agreement between our fit of $H\beta'_G = -0.017 \log \sigma_0 + 0.144$ and that from Kunstchner (2000) of $H\beta'_G = -0.026 \log \sigma_0 + 0.169$. The likely implication is that more massive galaxies are older relative to less massive galaxies.

Mgb' , however, we find is correlated with σ_0 . The usual explanation for this correlation is that larger ellipticals have a deeper potential and hence find it easier to hold on to heavier elements produced in supernova explosions than do smaller ellipticals. We obtain a fit of $Mgb' = 0.116 \log \sigma_0 + 0.144$ while the fit found by Colless et al. (1999) is $Mgb' = 0.131 \log \sigma_0 + 0.131$. The slopes agree quite well but there seems to be an offset between our fit and Colless et al. (1999). We also note an offset in Mgb between our clusters. Since previous results have found no significant change in the zero-point of this relation (e.g. Colless et al., 1999) we suspect this may be a data reduction issue, but it may possibly indicate cluster to cluster variations, contrary to previous results.

References

- Colless, M., Burstein, D., Davies, R. L. et al. 1999 *MNRAS* **303**, 813–825.
- Eggen, O. J., Lynden-Bell, D. & Sandage, A. R. 1962 *ApJ* **136** 748–766.
- Gonzalez, J. J. and Faber, S. M. and Worthey, G. 1993 *AAS* **25** 1355.
- Jørgensen, Inger 1999 *MNRAS* **306**, 607–636.
- Kuntschner, H. 2000 *MNRAS* **315**, 184–208.
- Moore, Stephen A. W., Lucey, John R., Kuntschner, Harald et al. 1998 *MNRAS* **336**, 382–408.
- Searle, L. & Zinn, R. 1978 *ApJ* **225**, 357–379.
- Thomas, D., Maraston, C. & Bender, R. 2002 *MNRAS* **339**, 897–911.
- Worthey, Guy 1994 *ApJS* **95**, 107–149.